THALWARA (FINAL PH)

SPECIAL INSTRUCTION / APPROVED SPECIAL INSTRUCTION

SL.NO.	INSTRUCTION	ISSUED BY	AUTHORITY	REMARKS
1.	PCOM'S SANCTION OBTAINED IN TERMS OF G.R. 3.47 FOR TAKING 'OFF' SIGNALS FOR MORE THAN ONE TRAIN AT A TIME WHEN TWO OR MORE TRAINS ARE APPROACHING AND/OR DEPARTING FROM ANY DIRECTION WHERE YARD LAYOUT PROVIDES ISOLATION BETWEEN SUCH MOVEMENTS.	PCOM/ECR/HJP		TO BE OBTAINED

CONDONATION PARTICULARS OF EXISTING INFRINGING GRADIENTS

SNo	LOCATIONS SECTION	KILOMETERAGE FROM	 TO	NAME OF STRUCTURE INFRINGING	RAILWAY BOARD / CRS CONDONATION PARTICULARS
NIL					

Signature block

CSTE/D&D/ECR	NIRAJ YADAV	Digitally signed by NIRAJ YADAV Date: 2025.01.13 17:09:53 +05'30'
CTPM/ECR	SUDHIR CHANDRA KUMAR	Digitally signed by SUDHIR CHANDRA KUMAR Date: 2025.01.13 15:08:48 +05'30'
CSTE/C/N/MHX	LALAN KUMAR RAM	Digitally signed by LALAN KUMAR RAM Date: 2025.01.10 17:12:05 +05'30'
SrDOM/SPJ	Vijay Prakash	Digitally signed by Vijay Prakash Date: 2025.01.09 00:05:28 +05'30'
SrDSTE/SPJ	PANKAJ KUMAR	2024.12.30 15:37:13 +05'30'
Dy.CSTE/C-II/N/MHX	Manish Kumar	Digitally signed by Manish Kumar Date: 2025.01.02 11:52:31 +05'30'
Dy.CSTE/C/D&D/MHX	BINOD KUMAR SINGH	Digitally signed by BINOD KUMAR SINGH Date: 2024.12.26 18:34:49 +05'30'
ASTE/C/North	Ashok Kumar Singh	Digitally signed by Ashok Kumar Singh Date: 2024.12.26 18:21:04 +05'30'
SSE/S/C/MHX	MANISH KUMAR SINHA	Digitally signed by MANISH KUMAR SINHA Date: 2024.12.26 17:40:11 +05'30'
JE/Drg/C/MHX	MOHIT KUMAR	Digitally signed by MOHIT KUMAR Date: 2024.12.26 17:43:41 +05'30'

F 1 IN 400
F 1 IN 1160
F 1 IN 556
LEVEL
CH:3064m FOR UP M/L
CH:2566m FOR UP M/L
CH:2257m FOR UP M/L
CH:3064m FOR DN M/L
CH:2566m FOR DN M/L
CH:2257m FOR DN M/L
F 1 IN 1500
CH:978m
F1 IN 11500
R 1 IN 3000m
CH:255m
R 1 IN 3000m
CH:1454m
F 1 IN 2850m
CH:1755m
CH:2326m
F 1 IN 1800m
CH:3097m
UP TO CH:3546m
N
DN
UP
C/L OF STN. BUILDING OF THALWARA (TLWA)
AT KM. 27.882 (FROM SPJ)
CH: 0.00m
S&T BUILDING (37 X 5.79m)
S.B.
HIGH LEVEL PASSENGER PLATFORM 600m
HIGH LEVEL PASSENGER PLATFORM (600mX8m)
1400m
1000m(MIN.)
180m(MIN.)
65m
120m(MIN.)
215m
348m
777m
608m
180m
1000m(MIN.)
1400m
423m
609m
NEXT BLOCK STN.:- HAYAGHAT (HYT)
AT km-21.706 (FROM SPJ)
km-6.176 (FROM TLWA)
TO SAMASTIPUR JN.
AT km-0.00 (FROM SPJ)
(km-27.882) (FROM TLWA)
WARNING BOARD (GOODS)
UP DIST. OF TLWA
D1
BR. NO.- 17A2 (1X4m RCC BOX)
AT km-26/2-3,CH-1634.085m
BR. NO.- 17A (1X6.10m PSC SLAB)
AT km-26/4-5,CH-1473.445m
BR. NO.- 18 (2X6.10m PSC SLAB) & (2X6m RCC BOX)
AT km-26/9-10,CH-977.716m
UP HOME SIG.
C1 S1
S2
DN ADV. STR.
4,6,104,106
NON INTERLOCKED
L-XING NO. 13,(M),E
CLASS-'C',CH:2254.9m
km-25/6-7,WIDTH - 5m
ANGLE OF CROSSING-90°
UP AXC (HYT-TLWA)
DN AXC (TLWA-HYT)
SH-201
51B 51BT 51AT 51A
52A 52B 52T
53A 53B
S4 104
S6 106
DSH204
DSH202
NO STABLING OVER RUN LINE 120m.
CAL-756.50m (FM TO PT)
CAL-756.50m (FM TO FM)
CAL-763m (FM TO FM)
CAL-763m (PT TO FM)
AXC L1
05T2 05T1
03T2 03T1
04T 04T1 04T2
06T 06/07T
1B,1B-ALT,C1B
1A,C1A
201L3
1C,C1C,201L4
UP LOOP LINE
UP MAIN LINE
DN MAIN LINE
COMMON LOOP LINE
CSL-743.5m (ST TO DSH)
CSL-750m (ST TO SH)
CSL-750m (ST TO ST)
LINE NO. -1
LINE NO. -2
LINE NO. -3
LINE NO. -4
206L1
206L2
12A,C12A,206L3
12B,12B-ALT,C12B,206L4
105 S5
103 S3
107 S7
SH-205
58A 58B
59A 59B 59BT
60A 60B 60AT 60BT
SH-206
KEY 'C' WILL GO TO GL EKT.
INTERLOCKED
C L-XING NO.15, (M),T.
CLASS-'A',CH.-255.126m
km-28/0-1, WIDTH-6.65m
ANGLE OF CROSSING-90°
CONTROLLED BY G-31
UP ADV. STR.
S11
3,5,7,103,105,107,205
011T 11T 11T1 12T 12T1 12T2 C - 12T
UP AXC (TLWA-LSI)
DN AXC (LSI-TLWA)
BR. NO.- 18A (1X6m RCC BOX)
AT km-28/6-7, CH:-718.05m
BR. NO.- 19 (1X1.5m RCC BOX)
AT km-28/6-7, CH-736m
INTERLOCKED
L-XING NO. 16,(M),T
CLASS-'C',CH:844.879m
km-28/6-7,WIDTH - 5.3m
ANGLE OF CROSSING-90°
KEY 'B' WILL GO TO GL EKT.
CONTROLLED BY G-32
DN HOME SIG.
S12 C12
INTERLOCKED
L-XING NO. 17,(M),E
CLASS-'SPL',CH:1453.52m
km-29/2-3,WIDTH - 5.55m
ANGLE OF CROSSING-90°
UP GATE SIG.
G1
KEY 'S' WILL GO TO GL EKT.
(CONTROLLED BY SW-1)
G2
DN GATE SIG.
D12
DN DIST. OF TLWA
WARNING BOARD (GOODS)
BR. NO.- 20 (2X3.11m RCC BOX)
CH-2325m, KM-30/2-3
NEXT BLOCK STN.:- LAHERIASARAI (LSI)
km-4.708 (FROM TLWA)
AT km-32.590 (FROM TLWA)
TO DARBHANGA (DBG)
AT km.- 37.42 FROM SPJ
km.- 9.538 FROM TLWA

ASPECT CONTROL CHART (DN DIRECTION)



(ADV. STR.) S2
(STR.) S4
(HOME) S12
(GATE SIG.) G2
(DIST.) D12
335m
1543m
609m
1000m
G
R
Y
YY
S6
YWU

ASPECT CONTROL CHART (UP DIRECTION)



(DIST.) D1
(HOME) S1
(STR.) S3
(ADV. STR.) S11
(GATE SIG.) G1
1000m
125m
381m
777m
G
YY
Y
R
YWU
S5
S5/7
S7

AT G.L. OF LC GATE NO. 15



EKT 'EB' EMERGENCY KEY
(ARMATURE REMOVED) SEALED & LOCKED IN GLASS BOX.
CONTROLLED BY G-31 EKT 'A'
'C'
KEY 'C' TO COME FROM EKT 'B' OR SLIDING BOOM
EKT 'B'
KEY 'C' TO COME OUT FROM EKT 'B' AFTER BOOM LOCKING AND CLOSING DETECTION CONTACTS
GATE OPEN SWITCH
GATE CLOSED SWITCH
GATE COMMON SWITCH

AT G.L. OF LC GATE NO. 16



EKT 'EB' EMERGENCY KEY
(ARMATURE REMOVED) SEALED & LOCKED IN GLASS BOX.
CONTROLLED BY G-32 EKT 'A'
'B'
KEY 'B' TO COME FROM EKT 'B' OR SLIDING BOOM
EKT 'B'
KEY 'B' TO COME OUT FROM EKT 'B' AFTER BOOM LOCKING AND CLOSING DETECTION CONTACTS
GATE OPEN SWITCH
GATE CLOSED SWITCH
GATE COMMON SWITCH

AT GATE LODGE OF LC NO. - 17



EKT 'EB' EMERGENCY KEY
(ARMATURE REMOVED) SEALED & LOCKED IN GLASS BOX.
CONTROLLED BY SW-1 EKT 'A'
'S'
KEY 'S' TO COME FROM EKT 'B' OR SLIDING BOOM
EKT 'B'
KEY 'S' TO COME OUT FROM EKT 'B' AFTER BOOM LOCKING AND CLOSING DETECTION CONTACTS
GATE OPEN SWITCH
GATE CLOSED SWITCH
GATE COMMON SWITCH
N R
SW-1 GATE CONTROL
SW-2 FOR DN GATE SIG. G-2
SW-3 FOR UP GATE SIG. G-1
SW-4 SPARE

SWITCH	DESCRIPTION
SW-1	GATE CONTROL
SW-2	DN GATE SIG.
SW-3	UP GATE SIG.
SW-4	SPARE

LOCKING TABLE FOR (LC No. 17)

SWITCH /SIG.	BACK LOCKS SWITCH/SIG.	LOCKS SWITCH/SIG.	RELEASES SWITCH/SIG.
1.	-	-	2,3
2.	1	-	-
3.	1	-	-
4.	SPARE		

SIGNAL SPECIFIC NOTES – II

9. DETAILS OF SIGNAL ROUTES HAVING ALTERNATE OVERLAPS

SIGNAL NO.	LEADING TO	DETAILS OF OVERLAP
S1	ROAD 1(L/N:-1)	UP TO DEAD END WHEN POINT 58 'N' UP TO T/C 3T WHEN POINT 58 'R' WITH G-31 OPEN
S1	ROAD 2(L/N:2)	UP TO T/C 3T WHEN POINT 58 'N' WITH G-31 OPEN
S1	ROAD 4(L/N:-4)	UP TO SAND HUMP WHEN POINT 59 'N'

SIGNAL NO.	LEADING TO	DETAILS OF OVERLAP
S12	ROAD 3(L/N:-3)	UP TO T/C 51AT WHEN POINT 53 'N', 51 'N'
S12	ROAD 4(L/N:-4)	UP TO DEAD END WHEN POINT 53 'N' UP TO T/C 51AT WHEN POINT 53 'R' & 51 'N'

10. 60 SEC. TIME DELAY PROVIDED FOR C-1 & C-12 SIGNAL.
11. ALL ANGLE OF XINGS ARE 1 IN 12 (CURVED SWITCH) EXCEPT AS MENTIONED.
12. SIGNAL OVERLAP-120m AND BLOCK OVERLAP-180m IS TAKEN.
13. LC GATE NO. 13 SITUATED AT km:-25/6-7, CH:2254.9m IS MECHANICALLY OPERATED LIFTING BARRIER, AND LC GATE NO. 15 SITUATED AT km:-28/0-1, CH: 255.126m, LC GATE NO. 16 SITUATED AT km 28/6-7, CH:-844.879m & LC GATE NO. 17 SITUATED AT km:-29/2-3, CH:-1453.52m ARE ELECTRICALLY OPERATED LIFTING BARRIER.
14. TWO CPU & VDU (ONE SET STAND BY) PROVIDED FOR VDU OPERATION IN ASM/SM ROOM AND ONE COLOUR MONITOR PROVIDED IN MAINTENANCE ROOM.
15. CONTROL TELEPHONE PROVIDED AT VDU ROOM.
16. ROAD SIGNAL SHALL BE RAISED BACK TO DANGER BEFORE MOVING OF SLIDING BOOM BARRIER TO CLOSE THE LC GATE.
17. DEAD APPROACH LOCKING PROVIDED FOR INTERLOCKED GATES OF BLOCK SECTION WITH 60 SEC. TIME DELAY.

18. V.D.U. DETAILS:-

MAIN SIGNAL – 1. 2. 3. 4. 5. 6. 7.11.12.
CALLING - ON SIGNAL – C-1. C-12.
SHUNT SIGNAL – 103. 104. 105. 106. 107. 201. 205. 206.
DEAD SHUNT SIGNAL – 202. 204
POINT – 51, 52, 53, 58, 59, 60.
SIDING POINT – NIL
CRANK HANDLE CONTROL – CH1, CH2, CH3, CH8, CH9, CH10.
L-'X' ING GATE CONTROL – G-31, G-32
FOULING TRACK CIRCUIT – NIL

19. L-XING DETAILS BETWEEN TLWA - HYT .

S.N.	L.C. NO.	CLASS	km.	(M/UM)	ENGG./ TRAFFIC	TVU MAR.-2021	TELE. CON. WITH STN.	INTERLOCKED/ NON-INTERLOCKED	REMARKS
1.	13	C	25/6-7	(M)	ENGG.	8550	TLWA	NON-INTERLOCKED	--

20. L-XING DETAILS BETWEEN TLWA- LSI .

S.N.	L.C. NO.	CLASS	km.	(M/UM)	ENGG./ TRAFFIC	TVU MAR.-2021	TELE. CON. WITH STN.	INTERLOCKED/ NON-INTERLOCKED	REMARKS
1.	15	A	28/0-1	M	TRAFFIC	41667	TLWA	INTERLOCKED	--
2.	16	C	28/6-7	M	TRAFFIC	19635	TLWA	INTERLOCKED	--
3.	17	SPL	29/2-3	M	ENGG.	76245	TLWA	INTERLOCKED	--
4.	18	SPL	30/9-31/0	M	TRAFFIC	261375	LSI	INTERLOCKED	--
5.	19	B2	31/3-4	M	TRAFFIC	20247	LSI	INTERLOCKED	--

21. STANDARD COLOUR SCHEME NEEDS TO BE ADOPTED FOR DEPICTING INTENDED ALTERATIONS IN THE SSP.
i) FOR NEW WORK:- RED COLOUR
ii) FOR DELETION WORK:- GREEN COLOUR.

SIGNAL SPECIFIC NOTES – I

1. NUMBER GRID:

FUNCTIONS	LOCATION or DIRECTION	RANGE	SPARES
SIGNAL	RIGHT TO LEFT	(02-30) (EVEN NUMBERS)	8,10, 14 to 30
	LEFT TO RIGHT	01-29 (ODD NUMBERS)	9, 13 to 29
SHUNT SIGNAL	RIGHT TO LEFT	202-260 (EVEN NUMBERS)	208 to 260
	LEFT TO RIGHT	201-259 (ODD NUMBERS)	203,207 to 259
POINTS	RIGHT HALF	58, 59, 60.	--
	LEFT HALF	51, 52, 53.	--
SIDING POINTS	RIGHT HALF	NIL	--
	LEFT HALF	NIL	--
LC GATE	RIGHT HALF	G-31,G-32, SW-1	--
	LEFT HALF	NIL	--

2. BLOCK WORKING:

SECTION	TYPE OF BLOCK WORKING	BLOCK INSTRUMENT TYPE	BPAC	REMARKS IF ANY
TLWA-LSI	ABSOLUTE BLOCK	UFSBI-DL	HASSDAC	LOCATED AT SM ROOM
TLWA-HYT	ABSOLUTE BLOCK	UFSBI-DL	HASSDAC	LOCATED AT SM ROOM

3. DETAILS OF TRACK CIRCUITS:

TRACK CIRCUIT NOS.	TYPE OF TRACK CIRCUITS	REMARKS IF ANY
C-1T, 1T, 51BT, 52T, 03T2, 03T1, 03T, 3T, 60BT, 011T, 11T, 11T1, 02T, 51AT, 4T, 04T, 04T1, 04T2, 59BT, 60AT, 12T2, 12T1, 12T, C-12T, (05T2, 05T1, 05T) & AXC-L1, 5T, 6T, 06T, 06/07T, 07T, 7T.	DC SINGLE RAIL TRACK CIRCUIT	-

4. DETAILS OF AXLE COUNTERS:

AXLE COUNTER SECTION	TYPE OF AXLE COUNTER	TYPE OF RESETTING	LOCATION OF RESETTING BOX	LOCATION OF CO OPERATION PLUNGER/LV BOX
HYT-TLWA (UP)	HASSDAC	PREPARATORY	AT HYT STN.	AT TLWA STN.
TLWA-LSI (UP)	HASSDAC	PREPARATORY	AT TLWA STN.	AT LSI STN.
LSI-TLWA (DN)	HASSDAC	PREPARATORY	AT LSI STN.	AT TLWA STN.
TLWA-HYT (DN)	HASSDAC	PREPARATORY	AT TLWA STN.	AT HYT STN.

5. DETAILS OF MOTOR OPERATED POINTS WITH CRANK HANDLE GROUPING:

GROUP	POINTS	TYPE OF POINT MACHINE	CH EKT KEPT AT
CH1	51	IRS POINT MACHINE	SM ROOM
CH2	52	IRS POINT MACHINE	SM ROOM
CH3	53	IRS POINT MACHINE	SM ROOM
CH8	58	IRS POINT MACHINE	SM ROOM
CH9	59	IRS POINT MACHINE	SM ROOM
CH10	60	IRS POINT MACHINE	SM ROOM

6. DETAILS OF SIDING POINTS:- NIL (IF ANY)
i. POINT NO :KL IS LOCALLY OPERATED WITH SUCCESSIVE KEY RELEASE ARRANGEMENT
ii. SIDING POINT KEY CONTROL IS TRANSMITTED TO SITE BY SM FOR OPERATION
iii. SIDING POINT KEY A IS EXTRACTED FROM EKT LOCATED AT SITE
iv. THIS KEY IS INSERTED TO UNLOCK A END POINT
v. SIDING POINT IS SET TO REVERSE AND KEY B IS EXTRACTED
vi. KEY B IS INSERTED AT OTHER END AND TRAP POINT IS SET TO REVERSE
vii. SIDING IS READY FOR SHUNTING
viii. SIDING POINT :- NIL IS PROVIDED WITH EPD FOR ENSURING ITS NORMAL DETECTION.

SIDING POINT DETECTION TABLE(Elec):

SIDING POINT NO.	DETECTS POINT NORMAL/REVERSE	PROVED IN SIGNAL NO.	LEADING TO
--	--	--	--

7. INTERLOCKED LC GATE DETAILS:
I. LC NO 15, 16 & 17 ARE PROVIDED WITH EOLB.
II. WINCH IS OPERATED TO CLOSE THE LC GATE AND WINCH KEY IS TAKEN OUT:- LC NO. 13.
III. WINCH KEY IS INSERTED IN BOOM LOCK LEVER TO RELEASE, AND BOOM LEVER IS REVERSED:- LC NO. 13
IV. BOOM LOCK KEY IS TAKEN OUT AND INSERTED IN EKT FOR TRANSMISSION TO STATION MASTER:- (FOR LC NO. 13)

8. COMMUNICATION DETAILS:
TELEPHONE COMMUNICATION IS PROVIDED BETWEEN SM AND LC NO 13, 15, 16 & 17 .
SIDING POINT KL:- NIL.

GENERAL NOTES

1. THIS PLAN IS BASED ON SIGNAL INTERLOCKING PLAN NO: ECR/SIP/SPJ/324/2019 (PH-I)
2. THIS PLAN IS BASED ON ENGINEERING SCALE PLAN (ESP) NO: Y-32-2024.
3. THIS PLAN SUPERSEDES SIP/SSP NO: ECR/SIP/SPJ/324/2019 (PH-I)
4. THIS STATION IS LOCATED IN 25 KV AC ELECTRIFIED SECTION.
5. ALL THE STOP SIGNALS ARE LOCATED CLEAR OFF NEUTRAL SECTION.
6. VISIBILITY OF NEW SIGNALS TO BE ENSURED BY SIGNAL SIGHTING COMMITTEE SUBJECT TO LIGHTING OF SIGNALS.
7. SYSTEM OF WORKING IS ABSOLUTE BLOCK SYSTEM.
8. LC GATE NO. 13 IS MECHANICALLY OPERATED.
9. NO APPROACH WARNING IS PROVIDED FOR THE LC GATE .
10. THE GROUND MOUNTED LEVER FRAMES ARE PROVIDED FOR SIDING POINT:- NIL OPERATION AND LC GATE BOOM LOCKING:- LC NO. 15, 16 & 17.
11. THE HPL IS PROVIDED FOR SIDING POINT AND STANDS NORMALLY IN . :- NIL
12. ALL THE WORKS ARE CARRIED OUT AS PER THE PROVISIONS IN THE SEM. G&SR AND OTHER POLICY LETTERS.
13. THE NEW EQUIPMENT IS PLACED AS PER SITE SURVEY.
14. RECORD OF DESIGN DECISIONS ARE DETAILED IN SCHEME PLAN DESIGN LOG : :-NIL
15. FOULING POINTS ARE REQUIRED TO BE MEASURED ON SITE.
16. SIGNAL AND SIGNAGES ARE IN ACCORDANCE WITH G&SR AND SEM.
17. THE CROSS OVER POINTS ARE OPERATED BY PARALLEL OPERATION.
18. POINT ZONE TELEPHONES (PTZ) ARE PROVIDED AT TOP POINTS:- NIL.
19. NON-STANDARD SYMBOLS USED ON THIS PLAN ARE . :- NIL.
20. LIST OF ASSUMPTION BEING MADE WHILE SCHEME PLAN WAS IN PRODUCTION ARE
(i) . . . .
(ii) . . . .
21. SCHEME PLAN SPECIFIC ISSUES WHICH ARE STILL TO BE RESOLVED
(i) . . . .
(ii) . . . .
22. TYPE OF INTERLOCKING : CENTRALISED ELECTRONIC INTERLOCKING.
23. REFER INTERLOCKING CONTROL CHART FOR DETAILS OF ALL SIGNAL ROUTES.
24. COMPLETION DETAILS TO BE INCORPORATED AFTER COMMISSIONING THE WORKS SUITING TO SITE CONDITIONS FOR GENERATING SIGNAL INTERLOCKING PLAN (RECORDS UPDATED).
25. SPECIAL NOTES RELATED TO SPECIFIC RAILWAY/ STATION LIKE SPT, EMERGENCY GATE KEY etc.
26. ALL MAIN SIGNALS, SUBSIDIARY SIGNALS, GROUND SHUNT SIGNALS, REPEATER SIGNALS, STANDARD AND MINIATURE INDICATORS, POSITION LIGHT JUNCTION INDICATORS ARE OF LED TYPE.
27. PROVISION OF 3 SEC. TIME DELAY IN CONCERNED HR CIRCUIT OF STARTER SIGNALS S3, S4, S5, S6, & S7, PLACED 3m FROM RESPECTIVE GLUED JOINTS.
28. INTER-SIGNAL DISTANCES SHOWN IN ASPECT CONTROL CHART ARE AT LEAST AS MENTIONED.
29. ISOLATION POINTS IN OVERLAP PORTION SHOULD BE RELEASED WITH OVERLAP.
30. LC GATE SHOULD BE OPENED AFTER CLEARANCE OF GATE TRACK CIRCUIT AS PER IRSEM PARA 14.1.8(a).
31. PROVING OF CLEARANCE OF BERTHING PORTION OF LINE NO. 1 PROVIDED THROUGH HASSDAC IN ADDITION TO BERTHING TRACK CIRCUIT.
32. AUTHORITY OF WORK- P.B. ITEM NO. 52 OF 2023 - 2024.
33. THIS SIP HAS BEEN PREPARED IN CONNECTION WITH DOUBLING WORK BETWEEN THALWARA & HAYAGHAT STATION OF SAMASTIPUR -DARBHANGA SECTION.

SPECIAL NOTE:-

(1) ALL ISOLATED SIMULTANEOUS MOVEMENTS AS PER GR. 3.47 ARE PERMITTED.
(2) NO NON-ISOLATED SIMULTANEOUS MOVEMENTS BEYOND 120m AS PER GR 3.47(1) ARE PERMITTED.
(3) NO NON- ISOLATED SIMULTANEOUS SHUNTING MOVEMENTS DURING RECEPTION OF TRAIN AS PER GR. 5.16 ARE PERMITTED.

APPROVAL PANEL

ALT	DESCRIPTION	REFERENCE	CHECKED BY JE/SSE/D/ /C/MHX	 SSE/S/C /MHX	 ASTE/ C/MHX	 DSTE/C/ MFP	 DY.CSTE/ C/D&D/MHX	COUNTER SIGNED BY FOR PCOM/ECR/HJP	APPROVED BY FOR PCSTE/ECR/HJP	CRS SANCTION NO. & DATE	DATE OF COMM.

THIS LINE IS ONLY PRINTED TO SCALE IF THIS LINE MEASURES 100mm.

C.R.S. SANCTION NO. DATE :- COMPLETED ON:-		SCALE (1:1000) LONGITUDINAL : 1cm = 10m TRANSVERSE : 1cm = 5 m		E.I. WITH CENTRAL OPERATION SIGNAL INTERLOCKING PLAN
CLASS	B	SIGNAL INTERLOCKING PLAN ECR/SIP/SPJ-TLWA/324/2024	ZONE	ECR
STANDARD OF INTERLOCKING	II		DIVISION	SPJ
SCALE	LONGITUDINAL 1cm=10m VERTICAL 1cm=5m		STATION CODE	TLWA
थलवारा		THALWARA		

THALWARA (FINAL PH)